TECHNICAL SERVICE MANUAL: HYDRAULIC SYSTEM

Document ID: TSB-HYD-2026-04 | Tata Hitachi ZX210 / EX200

System: High-Pressure Main Hydraulic Circuit & Pump Assembly

1. SYMPTOM DESCRIPTION & OBSERVATION

Slow boom movement, weak digging force under load, and hydraulic oil temperature exceeding 85 C after 30 minutes of continuous operation.

2. INSPECTION PROCEDURE

Measure main pump discharge pressure at test port MP1. Normal relief pressure is 280 to 320 bar. If pressure drops below 190 bar when oil warms up to 60 C, test pump case drain flow for internal bypass leakage.

3. CORRECTIVE REPAIR ACTION

Replace hydraulic pump assembly and seals. Clean main control valve spool. Refill with fresh ISO VG 46 hydraulic fluid. Verify pressure holds at 280 bar.